



**NOTES**

1. MINIMUM DEPTH OF COVER FROM THE TOP OF PIPE TO FINISHED GRADE SHALL BE 4'-6".
2. (\*) INDICATES MINIMUM RELATIVE COMPACTION USING MODIFIED PROCTOR (ASTM D-1557).
3. BEDDING MATERIAL SHALL BE IMPORTED SAND WHICH SHALL BE APPROVED BY DISTRICT PRIOR TO USING. BEDDING SHALL BE PLACED AT A MINIMUM DEPTH OF 12" ABOVE PIPE.
4. BEDDING MATERIAL SHALL BE DISTRIBUTED TO AN EVEN GRADE ACROSS THE WIDTH OF THE TRENCH PROFILE.
5. BACKFILL WITH ROCKS IN EXCESS OF 5" DIAMETER OR SHARP JAGGED ROCK SHALL NOT BE ALLOWED IN THE TRENCH AT ANY TIME FROM BOTTOM OF TRENCH TO FINISHED GRADE. ONLY SELECT MATERIAL SHALL BE USED.
6. COMPACTION SHALL BE ACCOMPLISHED BY APPROVED METHODS IN MAXIMUM 12" LIFTS ABOVE THE COMPACTED BEDDING MATERIALS.

NOT TO SCALE



East Greenacres Irrigation District

**Pipe Bedding and Backfill  
for Water Mains**

Approved by:

*Ann W. [Signature]*  
District Manager

5/19/15  
Date

Standard Drawing No.

**W-5**