



ITEM NO.	NO. REQD.	DESCRIPTION
1	2	APP. PIPE DIA THREADED PLUG
2	1	THREAD IRON PIPE COUPLING
3	1	MAIN SIZE MJ CAP W/ CONCENTRIC REDUCER
3A	1	APP. PIPE DIA. x 12" LONG GALVANIZED PIPE NIPPLE.
4	2	TYLER CAST IRON VALVE BOX W/16" TOP SECTION & LID. SERIES 6855 OR APPROVED EQUAL.
5	1	CONCRETE BLOCKING - APPROVED PRECAST OR POURED
6	1	APP PIPE DIA THREADED IRON PIPE TEE -- GALVANIZED
7	1	WATER MAIN, MINIMUM 3' PUP AT END
8	1	MAIN SIZE MJ CAP W/ APP. PIPE DIA TAPPED THREADS.
9	1	APP DIA IPxIP THREADED GATE VALVE W/ 2" OPER. NUT
10	4	DRILL 1/8" HOLE OR CUT 1/2" SLOT WITH CHOP SAW
11	1	APP DIA X REQUIRED LENGTH GALV. PIPE NIPPLE

NOTE: STANDARD 2" BLOW OFF ASSY. IS ADEQUATE FOR 6" AND SMALLER, 3" FOR 12" AND SMALLER. MAINS TO ACHIEVE 2.5' FT/SEC VELOCITY.

NOT TO SCALE

	East Greenacres Irrigation District	Approved by: 
	<h2 style="margin: 0;">Mainline Blowoff Assembly</h2>	2/24/16 Date
		Standard Drawing No. <h2 style="margin: 0;">W-9</h2>